### **Subpart J—Test Requirements**

### §192.501 Scope.

This subpart prescribes minimum leak-test and strength-test requirements for pipelines.

#### §192.503 General requirements.

- (a) No person may operate a new segment of pipeline, or return to service a segment of pipeline that has been relocated or replaced, until—
- (1) It has been tested in accordance with this subpart and §192.619 to substantiate the maximum allowable operating pressure; and
- (2) Each potentially hazardous leak has been located and eliminated.
- (b) The test medium must be liquid, air, natural gas, or inert gas that is—
- (1) Compatible with the material of which the pipeline is constructed;
- (2) Relatively free of sedimentary materials; and
- (3) Except for natural gas, nonflammable.
- (c) Except as provided in §192.505(a), if air, natural gas, or inert gas is used as the test medium, the following maximum hoop stress limitations apply:

Class location	Maximum hoop stress allowed as per- centage of SMYS	
	Natural gas	Air or inert gas
1 2 3 4	80 30 30 30	80 75 50 40

(d) Each joint used to tie in a test segment of pipeline is excepted from the specific test requirements of this subpart, but each non-welded joint must be leak tested at not less than its operating pressure.

[35 FR 13257, Aug. 19, 1970, as amended by Amdt. 192–58, 53 FR 1635, Jan. 21, 1988; Amdt. 192–60, 53 FR 36029, Sept. 16, 1988; Amdt. 192–60A, 54 FR 5485, Feb. 3, 1989]

#### §192.505 Strength test requirements for steel pipeline to operate at a hoop stress of 30 percent or more of SMYS.

(a) Except for service lines, each segment of a steel pipeline that is to operate at a hoop stress of 30 percent or more of SMYS must be strength tested in accordance with this section to sub-

stantiate the proposed maximum allowable operating pressure. In addition, in a Class 1 or Class 2 location, if there is a building intended for human occupancy within 300 feet of a pipeline, a hydrostatic test must be conducted to a test pressure of at least 125 percent of maximum operating pressure on that segment of the pipeline within 300 feet of such a building, but in no event may the test section be less than 600 feet unless the length of the newly installed or relocated pipe is less than 600 feet. However, if the buildings are evacuated while the hoop stress exceeds 50 percent of SMYS, air or inert gas may be used as the test medium.

- (b) In a Class 1 or Class 2 location, each compressor station regulator station, and measuring station, must be tested to at least Class 3 location test requirements.
- (c) Except as provided in paragraph (e) of this section, the strength test must be conducted by maintaining the pressure at or above the test pressure for at least 8 hours.
- (d) If a component other than pipe is the only item being replaced or added to a pipeline, a strength test after installation is not required, if the manufacturer of the component certifies that—
- (1) The component was tested to at least the pressure required for the pipeline to which it is being added; or
- (2) The component was manufactured under a quality control system that ensures that each item manufactured is at least equal in strength to a prototype and that the prototype was tested to at least the pressure required for the pipeline to which it is being added.
- (e) For fabricated units and short sections of pipe, for which a post installation test is impractical, a preinstallation strength test must be conducted by maintaining the pressure at or above the test pressure for at least 4 hours.

#### § 192.507 Test requirements for pipelines to operate at a hoop stress less than 30 percent of SMYS and at or above 100 p.s.i.g.

Except for service lines and plastic pipelines, each segment of a pipeline that is to be operated at a hoop stress less than 30 percent of SMYS and at or

§ 192.509

above 100 p.s.i.g. must be tested in accordance with the following:

- (a) The pipeline operator must use a test procedure that will ensure discovery of all potentially hazardous leaks in the segment being tested.
- (b) If, during the test, the segment is to be stressed to 20 percent or more of SMYS and natural gas, inert gas, or air is the test medium—
- (1) A leak test must be made at a pressure between 100 p.s.i.g. and the pressure required to produce a hoop stress of 20 percent of SMYS; or
- (2) The line must be walked to check for leaks while the hoop stress is held at approximately 20 percent of SMYS.
- (c) The pressure must be maintained at or above the test pressure for at least 1 hour.

[35 FR 13257, Aug. 19, 1970, as amended by Amdt. 192–58, 53 FR 1635, Jan. 21, 1988]

#### § 192.509 Test requirements for pipelines to operate below 100 p.s.i.g.

Except for service lines and plastic pipelines, each segment of a pipeline that is to be operated below 100 p.s.i.g. must be leak tested in accordance with the following:

- (a) The test procedure used must ensure discovery of all potentially hazardous leaks in the segment being tested.
- (b) Each main that is to be operated at less than 1 p.s.i.g. must be tested to at least 10 p.s.i.g. and each main to be operated at or above 1 p.s.i.g. must be tested to at least 90 p.s.i.g.

[35 FR 13257, Aug. 19, 1970, as amended by Amdt. 192–58, 53 FR 1635, Jan. 21, 1988]

## § 192.511 Test requirements for service lines.

- (a) Each segment of a service line (other than plastic) must be leak tested in accordance with this section before being placed in service. If feasible, the service line connection to the main must be included in the test; if not feasible, it must be given a leakage test at the operating pressure when placed in service.
- (b) Each segment of a service line (other than plastic) intended to be operated at a pressure of at least 1 p.s.i.g. but not more than 40 p.s.i.g. must be given a leak test at a pressure of not less than 50 p.s.i.g.

(c) Each segment of a service line (other than plastic) intended to be operated at pressures of more than 40 p.s.i.g. must be tested to at least 90 p.s.i.g., except that each segment of a steel service line stressed to 20 percent or more of SMYS must be tested in accordance with §192.507 of this subpart.

[35 FR 13257, Aug. 19, 1970, as amended by Amdt. 192-74, 61 FR 18517, Apr. 26, 1996]

# § 192.513 Test requirements for plastic pipelines.

- (a) Each segment of a plastic pipeline must be tested in accordance with this section.
- (b) The test procedure must insure discovery of all potentially hazardous leaks in the segment being tested.
- (c) The test pressure must be at least 150 percent of the maximum operating pressure or 50 psig, whichever is greater. However, the maximum test pressure may not be more than three times the pressure determined under §192.121, at a temperature not less than the pipe temperature during the test.
- (d) During the test, the temperature of thermoplastic material may not be more than 38 °C (100 °F), or the temperature at which the material's long-term hydrostatic strength has been determined under the listed specification, whichever is greater.

[35 FR 13257, Aug. 19, 1970, as amended by Amdt. 192–77, 61 FR 27793, June 3, 1996; 61 FR 45905, Aug. 30, 1996]

## §192.515 Environmental protection and safety requirements.

- (a) In conducting tests under this subpart, each operator shall insure that every reasonable precaution is taken to protect its employees and the general public during the testing. Whenever the hoop stress of the segment of the pipeline being tested will exceed 50 percent of SMYS, the operator shall take all practicable steps to keep persons not working on the testing operation outside of the testing area until the pressure is reduced to or below the proposed maximum allowable operating pressure.
- (b) The operator shall insure that the test medium is disposed of in a manner that will minimize damage to the environment.