operating earth station in coordination with the satellite system control center under the provisions of §25.272.

(e) Certification that the tests required by paragraph (c) of this section have been satisfactorily performed shall be provided to the Commission in notification that construction of the facilities has been completed as required by §25.133.

(f) Antennas less than 3 meters in diameter and antennas on simple (manual) drive mounts that are operated at a fixed site are exempt from the requirements of paragraphs (c) and (d) of this section provided that a detailed technical showing is made that confirms proper installation, pointing procedures, and polarization alignment and manufacturing quality control. These showing must also include a plan for periodic testing and field installation procedures and precautions.

(g) Records of the results of the tests required by this section must be maintained at the antenna site or the earth station operator's control center and be available for inspection.

[58 FR 13419, Mar. 11, 1993]

§25.133 Period of construction; certification of commencement of operation.

(a) Each license for an earth station governed by this part shall specify as a condition therein the period in which construction of facilities must be completed and station operation commenced. Construction of the earth station must be completed and the station must be brought into regular operation within 12 months from the date of the construction permit and/or license grant except as may be otherwise determined by the Commission for any particular application.

(b) Each license for a transmitting earth station included in this part shall also specify as a condition therein that upon the completion of construction, each licensee must file with the Commission a certification containing the following information: The name of the licensee; file number of the application; call sign of the antenna; date of the license; a certification that the facility as authorized has been completed and that each antenna facility has been tested and is within 2 dB of the pattern

specified in §25.209, §25.135 (NVNG MSS earth stations), or §25.213 (1.6/2.4 GHz Mobile-Satellite Service earth stations); the date on which the station became operational; and a statement that the station will remain operational during the license period unless the license is submitted for cancellation. For stations authorized under §25.115(c) of this part (Large Networks of Small Antennas operating in the 12/ 14 GHz bands) and §25.115(d) of this part (User Transceivers in the Mobile-Satellite Service), a certificate must be filed when the network is put into operation.

(c) If the facility does not meet the technical parameters set forth in §25.209, a request for a waiver must be submitted and approved by the Commission before operations may commence.

(d) Each receiving earth station licensed or registered pursuant to §25.131 must be constructed and placed into service within 6 months after coordination has been completed. Each licensee or registrant must file with the Commission a certification that the facility is completed and operating as provided in paragraph (b) of this section, with the exception of certification of antenna patterns.

[56 FR 24016, May 28, 1991, as amended at 58 FR 68059, Dec. 23, 1993; 59 FR 53327, Oct. 21, 1994]

§25.134 Licensing provisions of Very Small Aperture Terminal (VSAT) networks.

(a) All applications for digital VSAT networks with a maximum outbound downlink EIRP density of +6.0 dBW/4 kHz per carrier and earth station antennas with maximum input power density of -14 dBW/4 kHz and maximum hub EIRP of 78.3 dBW will be processed routinely. All applications for analog VSAT networks with maximum outbound downlink power densities of +13.0 dBW/4 kHz per carrier and maximum antenna input power densities of -8.0 dBW/4 kHz shall be processed routinely in accordance with Declaratory Order in the Matter of Routine Licensing of Earth Stations in the 6 GHz and 14 GHz Bands Using Antennas Less than 9 Meters and 5 Meters in Diameter, Respectively, for Both