

§ 25.133

§ 25.133 Period of construction; certification of commencement of operation.

(a) Each license for an earth station governed by this part shall specify as a condition therein the period in which construction of facilities must be completed and station operation commenced. Construction of the earth station must be completed and the station must be brought into regular operation within 12 months from the date of the construction permit and/or license grant except as may be otherwise determined by the Commission for any particular application.

(b) Each license for a transmitting earth station included in this part shall also specify as a condition therein that upon the completion of construction, each licensee must file with the Commission a certification containing the following information: The name of the licensee; file number of the application; call sign of the antenna; date of the license; a certification that the facility as authorized has been completed and that each antenna facility has been tested and is within 2 dB of the pattern specified in § 25.209, § 25.135 (NVNG MSS earth stations), or § 25.213 (1.6/2.4 GHz Mobile-Satellite Service earth stations); the date on which the station became operational; and a statement that the station will remain operational during the license period unless the license is submitted for cancellation. For stations authorized under § 25.115(c) of this part (Large Networks of Small Antennas operating in the 12/14 GHz bands) and § 25.115(d) of this part (User Transceivers in the Mobile-Satellite Service), a certificate must be filed when the network is put into operation.

(c) If the facility does not meet the technical parameters set forth in § 25.209, a request for a waiver must be submitted and approved by the Commission before operations may commence.

(d) Each receiving earth station licensed or registered pursuant to § 25.131 must be constructed and placed into service within 6 months after coordination has been completed. Each licensee or registrant must file with the Commission a certification that the facility is completed and operating as provided

47 CFR Ch. I (10–1–99 Edition)

in paragraph (b) of this section, with the exception of certification of antenna patterns.

[56 FR 24016, May 28, 1991, as amended at 58 FR 68059, Dec. 23, 1993; 59 FR 53327, Oct. 21, 1994]

§ 25.134 Licensing provisions of Very Small Aperture Terminal (VSAT) networks.

(a) All applications for digital VSAT networks with a maximum outbound downlink EIRP density of +6.0 dBW/4 kHz per carrier and earth station antennas with maximum input power density of –14 dBW/4 kHz and maximum hub EIRP of 78.3 dBW will be processed routinely. All applications for analog VSAT networks with maximum outbound downlink power densities of +13.0 dBW/4 kHz per carrier and maximum antenna input power densities of –8.0 dBW/4 kHz shall be processed routinely in accordance with Declaratory Order in the Matter of Routine Licensing of Earth Stations in the 6 GHz and 14 GHz Bands Using Antennas Less than 9 Meters and 5 Meters in Diameter, Respectively, for Both Full Transponder and Narrowband Transmissions, 2 FCC Rcd 2149 (1987) (Declaratory Order).

(b) Each applicant for digital and/or analog VSAT network authorization proposing to use transmitted satellite carrier EIRP densities in excess of +6.0 dBW/4 kHz and +13.0 dBW/4 kHz, respectively, and/or maximum antenna input power densities of –14.0 dBW/4 kHz and maximum hub EIRPs of 78.3 dBW and –8.0 dBW/4 kHz per carrier, respectively, shall conduct an engineering analysis using the Sharp, Adjacent Satellite Interference Analysis (ASIA) program. Applicants shall submit a complete description of those baseline parameters they use in conducting their analysis and tabular summaries of the ASIA program's output detailing potential interference shortfalls. Applicants shall also submit a narrative summary which must indicate whether there are margin shortfalls in any of the current baseline services as a result of the addition of the new applicant's high power service, and if so, how the applicant intends to resolve those margin shortfalls. Applicants shall submit link budget analyses of