## § 75.223

least one row of posts should be installed to limit the roadway width to 16 feet. These posts should be—

- (i) Extended from the entrance to the split through the intersection outby the pillar in which the split or lift is being made; and
- (ii) Spaced on not more than 5-foot centers.
- (e) Unsupported openings at intersections. Openings that create an intersection should be permanently supported or at least one row of temporary supports should be installed on not more than 5-foot centers across the opening before any other work or travel in the intersection.
- (f) ATRS systems in working sections where the mining height is below 30 inches. In working sections where the mining height is below 30 inches, an ATRS system should be used to the extent practicable during the installation of roof bolts with roof bolting machines and continuous-mining machines with integral roof bolters.
- (g) Longwall mining systems. (1) Systematic supplemental support should be installed throughout—
- (i) The tailgate entry of the first longwall panel prior to any mining; and
- (ii) In the proposed tailgate entry of each subsequent panel in advance of the frontal abutment stresses of the panel being mined.
- (2) When a ground failure prevents travel out of the section through the tailgate side of the longwall section, the roof control plan should address—
- (i) Notification of miners that the travelway is blocked;
- (ii) Re-instruction of miners regarding escapeways and escape procedures in the event of an emergency;
- (iii) Re-instruction of miners on the availability and use of self-contained self-rescue devices;
- (iv) Monitoring and evaluation of the air entering the longwall section;
- (v) Location and effectiveness of the two-way communication systems; and
- (vi) A means of transportation from the section to the main line.
- (3) The plan provisions addressed by paragraph (g)(2) of this section should remain in effect until a travelway is reestablished on the tailgate side of a longwall section.

# §75.223 Evaluation and revision of roof control plan.

- (a) Revisions of the roof control plan shall be proposed by the operator—
- (1) When conditions indicate that the plan is not suitable for controlling the roof, face, ribs, or coal or rock bursts; or
- (2) When accident and injury experience at the mine indicates the plan is inadequate. The accident and injury experience at each mine shall be reviewed at least every six months.
- (b) Each unplanned roof fall and rib fall and coal or rock burst that occurs in the active workings shall be plotted on a mine map if it—
- (1) Is above the anchorage zone where roof bolts are used;
  - (2) Impairs ventilation;
  - (3) Impedes passage of persons;
- (4) Causes miners to be withdrawn from the area affected; or
- (5) Disrupts regular mining activities for more than one hour.
- (c) The mine map on which roof falls are plotted shall be available at the mine site for inspection by authorized representatives of the Secretary and representatives of miners at the mine.
- (d) The roof control plan for each mine shall be reviewed every six months by an authorized representative of the Secretary. This review shall take into consideration any falls of the roof, face and ribs and the adequacy of the support systems used at the time.

[53 FR 2375, Jan. 27, 1988; 60 FR 33723, June 29, 1995]

## **Subpart D—Ventilation**

SOURCE: 61 FR 9829, Mar. 11, 1996, unless otherwise noted.

### § 75.300 Scope.

This subpart sets requirements for underground coal mine ventilation.

### § 75.301 Definitions.

In addition to the applicable definitions in §75.2, the following definitions apply in this subpart.

Air course. An entry or a set of entries separated from other entries by stoppings, overcasts, other ventilation control devices, or by solid blocks of coal or rock so that any mixing of air