

Minerals Management Service, Interior

§250.1617

and both outlets are piped to overboard lines and that each line downstream of the changeover nipple at the spool has a minimum internal diameter of 10 inches.

(d) The diverter sealing element and diverter valves shall be pressure tested to a minimum of 200 psi when nipped upon conductor casing. No more than 7 days shall elapse between subsequent pressure tests. The diverter sealing element, diverter valves, and diverter control systems (including the remote) shall be actuation tested, and the diverter lines shall be tested for flow prior to spudding and thereafter at least once each 24-hour period alternating between control stations. All test times and results shall be recorded in the driller's report.

[56 FR 32100, July 15, 1991. Redesignated at 63 FR 29479, May 29, 1998, as amended at 74 FR 46909, Sept. 14, 2009]

§250.1614 Mud program.

(a) The quantities, characteristics, use, and testing of drilling mud and the related drilling procedures shall be designed and implemented to prevent the loss of well control.

(b) The lessee shall comply with requirements concerning mud control, mud test and monitoring equipment, mud quantities, and safety precautions in enclosed mud handling areas as prescribed in §250.455 through §250.459 of this part, except that the installation of an operable degasser in the mud system as required in §250.456(g) is not required for sulphur operations.

[56 FR 32100, July 15, 1991. Redesignated and amended at 63 FR 29479, 29487, May 29, 1998; 68 FR 8435, Feb. 20, 2003]

§250.1615 Securing of wells.

A downhole-safety device such as a cement plug, bridge plug, or packer shall be timely installed when drilling operations are interrupted by events such as those that force evacuation of the drilling crew, prevent station keeping, or require repairs to major drilling units or well-control equipment. The use of blind-shear rams or pipe rams and an inside BOP may be approved by the District Manager in lieu of the above requirements if cap rock casing has been set.

§250.1616 Supervision, surveillance, and training.

(a) The lessee shall provide onsite supervision of drilling operations at all times.

(b) From the time drilling operations are initiated and until the well is completed or abandoned, a member of the drilling crew or the toolpusher shall maintain rig-floor surveillance continuously, unless the well is secured with BOP's, bridge plugs, packers, or cement plugs.

(c) Lessee and drilling contractor personnel shall be trained and qualified in accordance with the provisions of subpart O of this part. Records of specific training that lessee and drilling contractor personnel have successfully completed, the dates of completion, and the names and dates of the courses shall be maintained at the drill site.

§250.1617 Application for permit to drill.

(a) Before drilling a well under an approved Exploration Plan, Development and Production Plan, or Development Operations Coordination Document, you must file Form MMS-123, APD, with the District Manager for approval. The submission of your APD must be accompanied by payment of the service fee listed in §250.125. Before starting operations, you must receive written approval from the District Manager unless you received oral approval under §250.140.

(b) An APD shall include rated capacities of the proposed drilling unit and of major drilling equipment. After a drilling unit has been approved for use in an MMS district, the information need not be resubmitted unless required by the District Manager or there are changes in the equipment that affect the rated capacity of the unit.

(c) An APD shall include a fully completed Form MMS-123 and the following:

(1) A plat, drawn to a scale of 2,000 feet to the inch, showing the surface and subsurface location of the well to be drilled and of all the wells previously drilled in the vicinity from which information is available. For development wells on a lease, the wells previously drilled in the vicinity need