

§ 63.7083

section, for which construction or reconstruction began after December 20, 2002, if you met the applicability criteria in § 63.7081 at the time you began construction or reconstruction.

(d) A lime kiln or PSH operations system is reconstructed if it meets the criteria for reconstruction defined in § 63.2.

(e) An existing lime kiln is any lime kiln, and (if applicable) its associated lime cooler, that does not meet the definition of a new kiln of paragraph (b) of this section.

(f) An existing PSH operations system is any PHS operations system that does not meet the definition of a new PSH operations system in paragraph (c) of this section.

(g) A PSH operations system includes all equipment associated with PSH operations beginning at the processed stone storage bin(s) or open storage pile(s) and ending where the processed stone is fed into the kiln. It includes man-made processed stone storage bins (but not open processed stone storage piles), conveying system transfer points, bulk loading or unloading systems, screening operations, surge bins, bucket elevators, and belt conveyors. No other materials processing operations are subject to this subpart.

(h) Nuisance dust collectors on lime coolers are part of the lime materials processing operations and are not covered by this subpart.

(i) Lime hydrators are not subject to this subpart.

(j) Open material storage piles are not subject to this subpart.

§ 63.7083 When do I have to comply with this subpart?

(a) If you have a new affected source, you must comply with this subpart according to paragraphs (a)(1) and (2) of this section.

(1) If you start up your affected source before January 5, 2004, you must comply with the emission limitations no later than January 5, 2004, and you must have completed all applicable performance tests no later than July 5, 2004.

(2) If you start up your affected source after January 5, 2004, then you must comply with the emission limitations for new affected sources upon

40 CFR Ch. I (7-1-11 Edition)

startup of your affected source and you must have completed all applicable performance tests no later than 180 days after startup.

(b) If you have an existing affected source, you must comply with the applicable emission limitations for the existing affected source, and you must have completed all applicable performance tests no later than January 5, 2007.

(c) If you have an LMP that is an area source that increases its emissions or its potential to emit such that it becomes a major source of HAP, the deadlines specified in paragraphs (c)(1) and (2) of this section apply.

(1) New affected sources at your LMP you must be in compliance with this subpart upon startup.

(2) Existing affected sources at your LMP must be in compliance with this subpart within 3 years after your source becomes a major source of HAP.

(d) You must meet the notification requirements in § 63.7130 according to the schedule in § 63.7130 and in subpart A of this part. Some of the notifications must be submitted before you are required to comply with the emission limitations in this subpart.

EMISSION LIMITATIONS

§ 63.7090 What emission limitations must I meet?

(a) You must meet each emission limit in Table 1 to this subpart that applies to you.

(b) You must meet each operating limit in Table 2 to this subpart that applies to you.

GENERAL COMPLIANCE REQUIREMENTS

§ 63.7100 What are my general requirements for complying with this subpart?

(a) After your initial compliance date, you must be in compliance with the emission limitations (including operating limits) in this subpart at all times, except during periods of startup, shutdown, and malfunction.

(b) You must be in compliance with the opacity and visible emission (VE) limits in this subpart during the times specified in § 63.6(h)(1).

Environmental Protection Agency

§ 63.7110

(c) You must always operate and maintain your affected source, including air pollution control and monitoring equipment, according to the provisions in § 63.6(e)(1)(i).

(d) You must prepare and implement for each LMP, a written operations, maintenance, and monitoring (OM&M) plan. You must submit the plan to the applicable permitting authority for review and approval as part of the application for a 40 CFR part 70 or 40 CFR part 71 permit. Any subsequent changes to the plan must be submitted to the applicable permitting authority for review and approval. Pending approval by the applicable permitting authority of an initial or amended plan, you must comply with the provisions of the submitted plan. Each plan must contain the following information:

(1) Process and control device parameters to be monitored to determine compliance, along with established operating limits or ranges, as applicable, for each emission unit.

(2) A monitoring schedule for each emission unit.

(3) Procedures for the proper operation and maintenance of each emission unit and each air pollution control device used to meet the applicable emission limitations and operating limits in Tables 1 and 2 to this subpart, respectively.

(4) Procedures for the proper installation, operation, and maintenance of monitoring devices or systems used to determine compliance, including:

(i) Calibration and certification of accuracy of each monitoring device;

(ii) Performance and equipment specifications for the sample interface, parametric signal analyzer, and the data collection and reduction systems;

(iii) Ongoing operation and maintenance procedures in accordance with the general requirements of § 63.8(c)(1), (3), and (4)(ii); and

(iv) Ongoing data quality assurance procedures in accordance with the general requirements of § 63.8(d).

(5) Procedures for monitoring process and control device parameters.

(6) Corrective actions to be taken when process or operating parameters or add-on control device parameters deviate from the operating limits spec-

ified in Table 2 to this subpart, including:

(i) Procedures to determine and record the cause of a deviation or excursion, and the time the deviation or excursion began and ended; and

(ii) Procedures for recording the corrective action taken, the time corrective action was initiated, and the time and date the corrective action was completed.

(7) A maintenance schedule for each emission unit and control device that is consistent with the manufacturer's instructions and recommendations for routine and long-term maintenance.

(e) You must develop a written start-up, shutdown, and malfunction plan (SSMP) according to the provisions in § 63.6(e)(3).

[69 FR 416, Jan. 5, 2004, as amended at 71 FR 20467, Apr. 20, 2006]

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

§ 63.7110 By what date must I conduct performance tests and other initial compliance demonstrations?

(a) If you have an existing affected source, you must complete all applicable performance tests within January 5, 2007, according to the provisions in §§ 63.7(a)(2) and 63.7114.

(b) If you have a new affected source, and commenced construction or reconstruction between December 20, 2002, and January 5, 2004, you must demonstrate initial compliance with either the proposed emission limitation or the promulgated emission limitation no later than 180 calendar days after January 5, 2004 or within 180 calendar days after startup of the source, whichever is later, according to §§ 63.7(a)(2)(ix) and 63.7114.

(c) If you commenced construction or reconstruction between December 20, 2002, and January 5, 2004, and you chose to comply with the proposed emission limitation when demonstrating initial compliance, you must conduct a demonstration of compliance with the promulgated emission limitation within January 5, 2007 or after startup of the source, whichever is later, according to §§ 63.7(a)(2)(ix) and 63.7114.

(d) For each initial compliance requirement in Table 3 to this subpart