

## Environmental Protection Agency

## §63.7113

$E_j$  = PM emission limit (0.10 or 0.12) for kiln  $j$ , or for kiln/cooler combination  $j$ , lb/ton of stone feed.

$P_j$  = Stone feed rate to kiln  $j$ , ton/hr.

$m$  = Number of kilns and kiln/cooler combinations you are averaging at your LMP. You must include the same kilns in the calculation of  $E_T$  and  $E_{TN}$ . Kilns that have a PM emission limit of 0.60 lb/ton are ineligible for any averaging.

(h) Performance test results must be documented in complete test reports that contain the information required by paragraphs (h)(1) through (10) of this section, as well as all other relevant information. The plan to be followed during testing must be made available to the Administrator at least 60 days prior to testing.

(1) A brief description of the process and the air pollution control system;

(2) Sampling location description(s);

(3) A description of sampling and analytical procedures and any modifications to standard procedures;

(4) Test results, including opacity;

(5) Quality assurance procedures and results;

(6) Records of operating conditions during the test, preparation of standards, and calibration procedures;

(7) Raw data sheets for field sampling and field and laboratory analyses;

(8) Documentation of calculations;

(9) All data recorded and used to establish operating limits; and

(10) Any other information required by the test method.

(i) [Reserved]

(j) You must establish any applicable 3-hour block average operating limit indicated in Table 2 to this subpart according to the applicable requirements in Table 3 to this subpart and paragraphs (j)(1) through (4) of this section.

(1) Continuously record the parameter during the PM performance test and include the parameter record(s) in the performance test report.

(2) Determine the average parameter value for each 15-minute period of each test run.

(3) Calculate the test run average for the parameter by taking the average of all the 15-minute parameter values for the run.

(4) Calculate the 3-hour operating limit by taking the average of the three test run averages.

(k) For each building enclosing any PSH operations that is subject to a VE limit, you must conduct a VE check according to item 18 in Table 4 to this subpart, and in accordance with paragraphs (k)(1) through (3) of this section.

(1) Conduct visual inspections that consist of a visual survey of the building over the test period to identify if there are VE, other than condensed water vapor.

(2) Select a position at least 15 but not more 1,320 feet from each side of the building with the sun or other light source generally at your back.

(3) The observer conducting the VE checks need not be certified to conduct EPA Method 9 in appendix A to part 60 of this chapter, but must meet the training requirements as described in EPA Method 22 in appendix A to part 60 of this chapter.

(1) When determining compliance with the opacity standards for fugitive emissions from PSH operations in item 7 of Table 1 to this subpart, you must conduct EPA Method 9 in appendix A to part 60 of this chapter according to item 17 in Table 4 to this subpart, and in accordance with paragraphs (1)(1) through (3) of this section.

(1) The minimum distance between the observer and the emission source shall be 4.57 meters (15 feet).

(2) The observer shall, when possible, select a position that minimizes interference from other fugitive emission sources (*e.g.*, road dust). The required observer position relative to the sun must be followed.

(3) If you use wet dust suppression to control PM from PSH operations, a visible mist is sometimes generated by the spray. The water mist must not be confused with particulate matter emissions and is not to be considered VE. When a water mist of this nature is present, you must observe emissions at a point in the plume where the mist is no longer visible.

### §63.7113 What are my monitoring installation, operation, and maintenance requirements?

(a) You must install, operate, and maintain each continuous parameter monitoring system (CPMS) according to your OM&M plan required by

§63.7100(d) and paragraphs (a)(1) through (5) of this section, and you must install, operate, and maintain each continuous opacity monitoring system (COMS) as required by paragraph (g) of this section

(1) The CPMS must complete a minimum of one cycle of operation for each successive 15-minute period.

(2) To calculate a valid hourly value, you must have at least four equally spaced data values (or at least two, if that condition is included to allow for periodic calibration checks) for that hour from a CPMS that is not out of control according your OM&M plan, and use all valid data.

(3) To calculate the average for each 3-hour block averaging period, you must use all valid data, and you must have at least 66 percent of the hourly averages for that period using only hourly average values that are based on valid data (*i.e.*, not from out-of-control periods).

(4) You must conduct a performance evaluation of each CPMS in accordance with your OM&M plan.

(5) You must continuously operate and maintain the CPMS according to the OM&M plan, including, but not limited to, maintaining necessary parts for routine repairs of the monitoring equipment.

(b) For each flow measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and (b)(1) through (4) of this section.

(1) Use a flow sensor with a minimum tolerance of 2 percent of the flow rate.

(2) Reduce swirling flow or abnormal velocity distributions due to upstream and downstream disturbances.

(3) Conduct a flow sensor calibration check at least semiannually.

(4) At least monthly, inspect all components for integrity, all electrical connections for continuity, and all mechanical connections for leakage.

(c) For each pressure measurement device, you must meet the requirements in paragraphs (a)(1) through (5) and (c)(1) through (7) of this section.

(1) Locate the pressure sensor(s) in or as close to as possible a position that provides a representative measurement of the pressure.

(2) Minimize or eliminate pulsating pressure, vibration, and internal and external corrosion.

(3) Use a gauge with a minimum tolerance of 0.5 inch of water or a transducer with a minimum tolerance of 1 percent of the pressure range.

(4) Check pressure tap pluggage daily.

(5) Using a manometer, check gauge calibration quarterly and transducer calibration monthly.

(6) Conduct calibration checks any time the sensor exceeds the manufacturer's specified maximum operating pressure range or install a new pressure sensor.

(7) At least monthly, inspect all components for integrity, all electrical connections for continuity, and all mechanical connections for leakage.

(d) For each bag leak detection system (BLDS), you must meet any applicable requirements in paragraphs (a)(1) through (5) and (d)(1) through (8) of this section.

(1) The BLDS must be certified by the manufacturer to be capable of detecting PM emissions at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.

(2) The sensor on the BLDS must provide output of relative PM emissions.

(3) The BLDS must have an alarm that will sound automatically when it detects an increase in relative PM emissions greater than a preset level.

(4) The alarm must be located in an area where appropriate plant personnel will be able to hear it.

(5) For a positive-pressure fabric filter (FF), each compartment or cell must have a bag leak detector (BLD). For a negative-pressure or induced-air FF, the BLD must be installed downstream of the FF. If multiple BLD are required (for either type of FF), the detectors may share the system instrumentation and alarm.

(6) Bag leak detection systems must be installed, operated, adjusted, and maintained according to the manufacturer's written specifications and recommendations. Standard operating procedures must be incorporated into the OM&M plan.

## Environmental Protection Agency

## §63.7114

(7) At a minimum, initial adjustment of the system must consist of establishing the baseline output in both of the following ways:

(i) Adjust the range and the averaging period of the device.

(ii) Establish the alarm set points and the alarm delay time.

(8) After initial adjustment, the range, averaging period, alarm set points, or alarm delay time may not be adjusted except as specified in the OM&M plan required by §63.7100(d). In no event may the range be increased by more than 100 percent or decreased by more than 50 percent over a 365-day period unless a responsible official, as defined in §63.2, certifies in writing to the Administrator that the FF has been inspected and found to be in good operating condition.

(e) For each PM detector, you must meet any applicable requirements in paragraphs (a)(1) through (5) and (e)(1) through (8) of this section.

(1) The PM detector must be certified by the manufacturer to be capable of detecting PM emissions at concentrations of 10 milligrams per actual cubic meter (0.0044 grains per actual cubic foot) or less.

(2) The sensor on the PM detector must provide output of relative PM emissions.

(3) The PM detector must have an alarm that will sound automatically when it detects an increase in relative PM emissions greater than a preset level.

(4) The alarm must be located in an area where appropriate plant personnel will be able to hear it.

(5) For a positive-pressure electrostatic precipitator (ESP), each compartment must have a PM detector. For a negative-pressure or induced-air ESP, the PM detector must be installed downstream of the ESP. If multiple PM detectors are required (for either type of ESP), the detectors may share the system instrumentation and alarm.

(6) Particulate matter detectors must be installed, operated, adjusted, and maintained according to the manufacturer's written specifications and recommendations. Standard operating procedures must be incorporated into the OM&M plan.

(7) At a minimum, initial adjustment of the system must consist of establishing the baseline output in both of the following ways:

(i) Adjust the range and the averaging period of the device.

(ii) Establish the alarm set points and the alarm delay time.

(8) After initial adjustment, the range, averaging period, alarm set points, or alarm delay time may not be adjusted except as specified in the OM&M plan required by §63.7100(d). In no event may the range be increased by more than 100 percent or decreased by more than 50 percent over a 365-day period unless a responsible official as defined in §63.2 certifies in writing to the Administrator that the ESP has been inspected and found to be in good operating condition.

(f) For each emission unit equipped with an add-on air pollution control device, you must inspect each capture/collection and closed vent system at least once each calendar year to ensure that each system is operating in accordance with the operating requirements in item 6 of Table 2 to this subpart and record the results of each inspection.

(g) For each COMS used to monitor an add-on air pollution control device, you must meet the requirements in paragraphs (g)(1) and (2) of this section.

(1) Install the COMS at the outlet of the control device.

(2) Install, maintain, calibrate, and operate the COMS as required by 40 CFR part 63, subpart A, General Provisions and according to Performance Specification (PS)-1 of appendix B to part 60 of this chapter. Facilities that operate COMS installed on or before February 6, 2001, may continue to meet the requirements in effect at the time of COMS installation unless specifically required to re-certify the COMS by their permitting authority.

### **§63.7114 How do I demonstrate initial compliance with the emission limitations standard?**

(a) You must demonstrate initial compliance with each emission limit in Table 1 to this subpart that applies to you, according to Table 3 to this subpart. For existing lime kilns and their associated coolers, you may perform