rest" position and released so as to permit a free fall of 6 feet (1.83 m) vertically below the point of attachment of the terminal anchor. The belt system should be equipped with devices and instrumentation capable of measuring the duration and magnitude of the arrest forces. Any breakage or slippage which permits the weight to fall free of the system constitutes failure of the test. In addition, the initial and subsequent arresting force peaks should be measured and should not exceed 2,000 pounds (8.9 Kn) for more than 2 milliseconds for the initial impact, nor exceed 1,000 pounds (4.45 Kn) for the remainder of the arrest time.

(4) All other positioning device systems (except for restraint line systems) should withstand a drop test consisting of a 250pound (113.4 kg) weight falling free for a distance of 4 feet (1.22 m). The weight should be a rigid object with a girth of 38 inches plus or minus 4 inches (96.52 cm plus or minus 10.16 cm). The body belt or harness should be affixed to the test weight as it would be to an employee. The system should be connected to the rigid anchor in the manner that the system would be connected in normal use. The weight should be lifted exactly 4 feet (1.22 m) above its "at rest" position and released so as to permit a vertical free fall of 4 feet (1.22 m). Any breakage or slippage which permits the weight to fall free to the ground should constitute failure of the system.

[47 FR 16986, Apr. 20, 1982, as amended at 67 FR 44544, July 3, 2002]

Subpart J—Ship's Machinery and Piping Systems

§ 1915.161 Scope and application of subpart.

The standards contained in this subpart shall apply to ship repairing and shipbuilding and shall not apply to shipbreaking.

§ 1915.162 Ship's boilers.

- (a) Before work is performed in the fire, steam, or water spaces of a boiler where employees may be subject to injury from the direct escape of a high temperature medium such as steam, or water, oil, or other medium at a high temperature entering from an interconnecting system, the employer shall insure that the following steps are taken:
- (1) The isolation and shutoff valves connecting the dead boiler with the live system or systems shall be secured, blanked, and then locked or

tagged, in accordance with §1915.89, indicating that employees are working on the boiler. This lock or tag shall not be removed nor the valves unblanked until it is determined that this may be done without creating a hazard to the employees working on the boiler, or until the work on the boiler is completed, in accordance with §1915.89. When valves are welded instead of bolted, at least two isolation and shutoff valves connecting the dead boiler with the live system or systems shall be secured, and then locked or tagged, in accordance with §1915.89.

- (2) Drain connections to atmosphere on all of the dead interconnecting systems shall be opened for visual observation of drainage.
- (3) A warning sign calling attention to the fact that employees are working in the boilers shall be hung in a conspicuous location in the engine room. This sign shall not be removed until it is determined that the work is completed and all employees are out of the boilers.

 $[47\ FR\ 16986,\ Apr.\ 20,\ 1982,\ as\ amended\ at\ 76\ FR\ 24711,\ May\ 2,\ 2011]$

§1915.163 Ship's piping systems.

- (a) Before work is performed on a valve, fitting, or section of piping in a piping system where employees may be subject to injury from the direct escape of steam, or water, oil, or other medium at a high temperature, the employer shall insure that the following steps are taken:
- (1) The isolation and shutoff valves connecting the dead system with the live system or systems shall be secured, blanked, and then locked or tagged, in accordance with §1915.89, indicating that employees are working on the systems. The lock or tag shall not be removed or the valves unblanked until it is determined that this may be done without creating a hazard to the employees working on the system, or until the work on the system is completed, in accordance with §1915.89. When valves are welded instead of bolted, at least two isolation and shutoff valves connecting the dead system with the live system or systems shall be secured, and then locked or tagged, in accordance with §1915.89.