

§ 250.911 If my platform is subject to the Platform Verification Program, what must I do?

If your platform, conversion, or major modification or repair meets the criteria in §250.910, you must:

(a) Design, fabricate, install, use, maintain and inspect your platform, conversion, or major modification or repair to your platform according to the requirements of this subpart, and the applicable documents listed in §250.901(a) of this subpart;

(b) Comply with all the requirements of the Platform Approval Program found in §§250.904 through 250.908 of this subpart.

(c) Submit for the Regional Supervisor's approval three copies each of the design verification, fabrication verification, and installation verification plans required by §250.912;

(d) Submit a complete schedule of all phases of design, fabrication, and installation for the Regional Supervisor's approval. You must include a project management timeline, Gantt Chart, that depicts when interim and final reports required by §§250.916, 250.917, and 250.918 will be submitted to the Regional Supervisor for each phase. On the timeline, you must break-out the specific scopes of work that inherently stand alone (e.g., deck, mooring systems, tendon systems, riser systems, turret systems).

(e) Include your nomination of a Certified Verification Agent (CVA) as a part of each verification plan required by §250.912;

(f) Follow the additional requirements in §§250.913 through 250.918;

(g) Obtain approval for modifications to approved plans and for major deviations from approved installation procedures from the Regional Supervisor; and

(h) Comply with applicable USCG regulations for floating OCS facilities.

§ 250.912 What plans must I submit under the Platform Verification Program?

If your platform, associated structure, or major modification meets the criteria in §250.910, you must submit the following plans to the Regional Supervisor for approval:

(a) *Design verification plan.* You may submit your design verification plan to BSEE with or subsequent to the submittal of your Development and Production Plan (DPP) or Development Operations Coordination Document (DOCD) to BOEM. Your design verification must be conducted by, or be under the direct supervision of, a registered professional civil or structural engineer or equivalent, or a naval architect or marine engineer or equivalent, with previous experience in directing the design of similar facilities, systems, structures, or equipment. For floating platforms, you must ensure that the requirements of the USCG for structural integrity and stability, e.g., verification of center of gravity, *etc.*, have been met. Your design verification plan must include the following:

(1) All design documentation specified in §250.905 of this subpart;

(2) Abstracts of the computer programs used in the design process; and

(3) A summary of the major design considerations and the approach to be used to verify the validity of these design considerations.

(b) *Fabrication verification plan.* The Regional Supervisor must approve your fabrication verification plan before you may initiate any related operations. Your fabrication verification plan must include the following:

(1) Fabrication drawings and material specifications for artificial island structures and major members of concrete-gravity and steel-gravity structures;

(2) For jacket and floating structures, all the primary load-bearing members included in the space-frame analysis; and

(3) A summary description of the following:

(i) Structural tolerances;

(ii) Welding procedures;

(iii) Material (concrete, gravel, or silt) placement methods;

(iv) Fabrication standards;

(v) Material quality-control procedures;

(vi) Methods and extent of non-destructive examinations for welds and materials; and

(vii) Quality assurance procedures.

§ 250.913

(c) *Installation verification plan.* The Regional Supervisor must approve your installation verification plan before you may initiate any related operations. Your installation verification plan must include:

- (1) A summary description of the planned marine operations;
- (2) Contingencies considered;
- (3) Alternative courses of action; and
- (4) An identification of the areas to be inspected. You must specify the acceptance and rejection criteria to be used for any inspections conducted during installation, and for the post-installation verification inspection.

(d) You must combine fabrication verification and installation verification plans for manmade islands or platforms fabricated and installed in place.

§ 250.913 When must I resubmit Platform Verification Program plans?

(a) You must resubmit any design verification, fabrication verification, or installation verification plan to the Regional Supervisor for approval if:

- (1) The CVA changes;
- (2) The CVA's or assigned personnel's qualifications change; or
- (3) The level of work to be performed changes.

(b) If only part of a verification plan is affected by one of the changes described in paragraph (a) of this section, you can resubmit only the affected part. You do not have to resubmit the summary of technical details unless you make changes in the technical details.

§ 250.914 How do I nominate a CVA?

(a) As part of your design verification, fabrication verification, or installation verification plan, you must nominate a CVA for the Regional Supervisor's approval. You must specify whether the nomination is for the design, fabrication, or installation phase of verification, or for any combination of these phases.

(b) For each CVA, you must submit a list of documents to be forwarded to the CVA, and a qualification statement that includes the following:

- (1) Previous experience in third-party verification or experience in the design, fabrication, installation, or major

30 CFR Ch. II (7-1-12 Edition)

modification of offshore oil and gas platforms. This should include fixed platforms, floating platforms, man-made islands, other similar marine structures, and related systems and equipment;

- (2) Technical capabilities of the individual or the primary staff for the specific project;
- (3) Size and type of organization or corporation;
- (4) In-house availability of, or access to, appropriate technology. This should include computer programs, hardware, and testing materials and equipment;
- (5) Ability to perform the CVA functions for the specific project considering current commitments;
- (6) Previous experience with BSEE requirements and procedures;
- (7) The level of work to be performed by the CVA.

§ 250.915 What are the CVA's primary responsibilities?

(a) The CVA must conduct specified reviews according to §§ 250.916, 250.917, and 250.918 of this subpart.

(b) Individuals or organizations acting as CVAs must not function in any capacity that would create a conflict of interest, or the appearance of a conflict of interest.

(c) The CVA must consider the applicable provisions of the documents listed in § 250.901(a); the alternative codes, rules, and standards approved under § 250.901(b); and the requirements of this subpart.

(d) The CVA is the primary contact with the Regional Supervisor and is directly responsible for providing immediate reports of all incidents that affect the design, fabrication and installation of the platform.

§ 250.916 What are the CVA's primary duties during the design phase?

(a) The CVA must use good engineering judgment and practices in conducting an independent assessment of the design of the platform, major modification, or repair. The CVA must ensure that the platform, major modification, or repair is designed to withstand the environmental and functional load conditions appropriate for the intended service life at the proposed location.