§63.7083

section, for which construction or reconstruction began after December 20, 2002, if you met the applicability criteria in §63.7081 at the time you began construction or reconstruction.

- (d) A lime kiln or PSH operations system is reconstructed if it meets the criteria for reconstruction defined in §63.2.
- (e) An existing lime kiln is any lime kiln, and (if applicable) its associated lime cooler, that does not meet the definition of a new kiln of paragraph (b) of this section.
- (f) An existing PSH operations system is any PHS operations system that does not meet the definition of a new PSH operations system in paragraph (c) of this section.
- (g) A PSH operations system includes all equipment associated with PSH operations beginning at the processed stone storage bin(s) or open storage pile(s) and ending where the processed stone is fed into the kiln. It includes man-made processed stone storage bins (but not open processed stone storage piles), conveying system transfer points, bulk loading or unloading systems, screening operations, surge bins, bucket elevators, and belt conveyors. No other materials processing operations are subject to this subpart.
- (h) Nuisance dust collectors on lime coolers are part of the lime materials processing operations and are not covered by this subpart.
- (i) Lime hydrators are not subject to this subpart.
- (j) Open material storage piles are not subject to this subpart.

§ 63.7083 When do I have to comply with this subpart?

- (a) If you have a new affected source, you must comply with this subpart according to paragraphs (a)(1) and (2) of this section.
- (1) If you start up your affected source before January 5, 2004, you must comply with the emission limitations no later than January 5, 2004, and you must have completed all applicable performance tests no later than July 5, 2004.
- (2) If you start up your affected source after January 5, 2004, then you must comply with the emission limitations for new affected sources upon

startup of your affected source and you must have completed all applicable performance tests no later than 180 days after startup.

- (b) If you have an existing affected source, you must comply with the applicable emission limitations for the existing affected source, and you must have completed all applicable performance tests no later than January 5, 2007
- (c) If you have an LMP that is an area source that increases its emissions or its potential to emit such that it becomes a major source of HAP, the deadlines specified in paragraphs (c)(1) and (2) of this section apply.
- (1) New affected sources at your LMP you must be in compliance with this subpart upon startup.
- (2) Existing affected sources at your LMP must be in compliance with this subpart within 3 years after your source becomes a major source of HAP.
- (d) You must meet the notification requirements in §63.7130 according to the schedule in §63.7130 and in subpart A of this part. Some of the notifications must be submitted before you are required to comply with the emission limitations in this subpart.

EMISSION LIMITATIONS

§ 63.7090 What emission limitations must I meet?

- (a) You must meet each emission limit in Table 1 to this subpart that applies to you.
- (b) You must meet each operating limit in Table 2 to this subpart that applies to you.

GENERAL COMPLIANCE REQUIREMENTS

§ 63.7100 What are my general requirements for complying with this subpart?

- (a) After your initial compliance date, you must be in compliance with the emission limitations (including operating limits) in this subpart at all times, except during periods of startup, shutdown, and malfunction.
- (b) You must be in compliance with the opacity and visible emission (VE) limits in this subpart during the times specified in $\S63.6(h)(1)$.