§ 60.154

- (1) Continuous operation of the monitoring devices and data recorders in paragraphs (a)(1), (b)(3), and (b)(4) of this section shall not be required.
- (2) Daily sampling and analysis of sludge feed in paragraph (b)(5) of this section shall not be required.
- (3) Recordkeeping specified in paragraph (c)(3) of this section shall not be required.
- (e) The owner or operator of any sludge incinerator other than a multiple hearth, fluidized bed, or electric incinerator or any sludge incinerator equipped with a control device other than a wet scrubber shall submit to the Administrator for approval a plan for monitoring and recording incinerator and control device operation parameters. The plan shall be submitted to the Administrator:
- (1) No later than 90 days after October 6, 1988, for sources which have provided notification of commencement of construction prior to October 6, 1988.
- (2) No later than 90 days after the notification of commencement of construction, for sources which provide notification of commencement of construction on or after October 6, 1988.
- (3) At least 90 days prior to the date on which the new control device becomes operative, for sources switching to a control device other than a wet scrubber.

[36 FR 24877, Dec. 23, 1971, as amended at 53 FR 39416, Oct. 6, 1988; 65 FR 61756, Oct. 17, 2000]

§ 60.154 Test methods and procedures.

- (a) In conducting the performance tests required in §60.8, the owner or operator shall use as reference methods and procedures the test methods in appendix A of this part or other methods and procedures as specified in this section, except as provided for in §60.8(b).
- (b) The owner or operator shall determine compliance with the particulate matter emission standards in §60.152 as follows:
- (1) The emission rate (E) of particulate matter for each run shall be computed using the following equation:

$$E = \frac{c_s Q_{sd}}{KS}$$

Where:

- E = Emission rate of particulate matter, g/kg (lb/ton) of dry sludge input.
- c_s = Concentration of particulate matter, g/dscm (gr/dscf).
- Q_{sd} = Volumetric flow rate of effluent gas, dscm/hr (dscf/hr).
- S = Charging rate of dry sludge during the run, kg/hr (ton/hr).
- K = Conversion factor, 1.0 g/g (7,000 gr/lb).
- (2) Method 5 shall be used to determine the particulate matter concentration (c_s) and the volumetric flow rate (Q_{sd}) of the effluent gas. The sampling time and sample volume for each run shall be at least 60 minutes and 0.90 dscm (31.8 dscf).
- (3) The dry sludge charging rate (S) for each run shall be computed using either of the following equations:

$$S = S_m R_{dm}/\Theta$$
$$S = S_v R_{dv}/K_v \Theta$$

Where:

S = Charging rate of dry sludge, kg/hr (ton/

 S_m = Total mass of sludge charge, kg (ton).

 $R_{\rm dm}$ = Average mass of dry sludge per unit mass of sludge charged, kg/kg (ton/ton).

 θ = Duration of run, hr.

 $S_{\rm v}$ = Total volume of sludge charged, m^3 (gal).

 R_{dv} = Average mass of dry sludge per unit volume of sludge charged, kg/m³ (lb/gal).

 K_v = Conversion factor, 1 g/g (2,000 lb/ton).

(4) the flow measuring device of $\S 60.153(a)(1)$ shall be used to determine the total mass (S_m) or volume (S_v) of sludge charged to the incinerator during each run. If the flow measuring device is on a time rate basis, readings shall be taken and recorded at 5-minute intervals during the run and the total charge of sludge shall be computed using the following equations, as applicable:

$$S_{m} = \sum_{i=1}^{n} Q /_{mi} \theta_{i}$$

$$S_{v} = \sum_{i=1}^{n} \frac{Q_{vi}}{\theta_{i}}$$

Where:

 $\mathbf{S}_{m}=\mathbf{Total}$ mass of sludge charged to the incinerator during the test run.

 \mathbf{S}_{v} = Total volume of sludge charged to the incinerator during the test run.

Environmental Protection Agency

- $\begin{array}{lll} Q_{mi} = & Average \ mass \ flow \ rate \ calculated \ by \\ & averaging \ the \ flow \ rates \ at \ the \ beginning \\ & and \ end \ of \ each \ interval \ ``i,'' \ kg/hr \ (ton/hr). \\ & Q_{vi} = & Average \ volume \ flow \ rate \ calculated \ by \\ & averaging \ the \ flow \ rates \ at \ the \ beginning \\ & and \ end \ of \ each \ interval \ ``i,'' \ m^3/hr \ (gal/hr). \\ & \theta_i = & Duration \ of \ interval \ ``i,'' \ hr. \end{array}$
- (5) Samples of the sludge charged to the incinerator shall be collected in nonporous jars at the beginning of each run and at approximately 1-hour intervals thereafter until the test ends, and "209 F. Method for Solid and Semisolid Samples" (incorporated by reference—see §60.17) shall be used to determine dry sludge content of each sample (total solids residue), except that:
- (i) Evaporating dishes shall be ignited to at least 103 °C rather than the 550 °C specified in step 3(a)(1).
- (ii) Determination of volatile residue, step 3(b) may be deleted.
- (iii) The quantity of dry sludge per unit sludge charged shall be determined in terms of kg/m³ (lb/gal) or kg/kg (ton/ton).
- (iv) The average dry sludge content shall be the arithmetic average of all the samples taken during the run.
- (6) Method 9 and the procedures in §60.11 shall be used to determine opacity.
 - (c) [Reserved]
- (d) The owner or operator of any sludge incinerator subject to the provisions of this subpart shall conduct a performance test during which the monitoring and recording devices required under §60.153(a)(1), (b)(1), (b)(2), (b)(3), and (b)(4) are installed and operating and for which the sampling and analysis procedures required under §60.153(b)(5) are performed. The owner or operator shall provide the Administrator at least 30 days prior notice of the performance test to afford the Administrator the opportunity to have an observer present.
- (1) For incinerators that commenced construction or modification on or before April 18, 1986, the performance test shall be conducted within 360 days of the effective date of these regulations unless the monitoring and recording devices required under §60.153(a)(1), (b)(1), (b)(2), (b)(3), and (b)(4) were installed and operating and the sampling and analysis procedures required under §60.153(b)(5) were performed during the most recent performance test and a

record of the measurements taken during the performance test is available.

(2) For incinerators that commence construction or modification after April 18, 1986, the date of the performance test shall be determined by the requirements in § 60.8.

[54 FR 6668, Feb. 14, 1989, as amended at 54 FR 27015, June 27, 1989; 59 FR 5108, Feb. 3, 1994; 65 FR 61756, Oct. 17, 2000]

§ 60.155 Reporting.

- (a) The owner or operator of any multiple hearth, fluidized bed, or electric sludge incinerator subject to the provisions of this subpart shall submit to the Administrator semi-annually a report in writing which contains the following:
- (1) A record of average scrubber pressure drop measurements for each period of 15 minutes duration or more during which the pressure drop of the scrubber was less than, by a percentage specified below, the average scrubber pressure drop measured during the most recent performance test. The percent reduction in scrubber pressure drop for which a report is required shall be determined as follows:
- (i) For incinerators that achieved an average particulate matter emission rate of 0.38 kg/Mg (0.75 lb/ton) dry sludge input or less during the most recent performance test, a scrubber pressure drop reduction of more than 30 percent from the average scrubber pressure drop recorded during the most recent performance test shall be reported.
- (ii) For incinerators that achieved an average particulate matter emission rate of greater than 0.38 kg/Mg (0.75 lb/ton) dry sludge input during the most recent performance test, a percent reduction in pressure drop greater than that calculated according to the following equation shall be reported:

P = -111E + 72.15

where P=Percent reduction in pressure drop, and

- E=Average particulate matter emissions (kg/megagram)
- (2) A record of average oxygen content in the incinerator exhaust gas for each period of 1-hour duration or more that the oxygen content of the incinerator exhaust gas exceeds the average