the design and construction of all diversions of perennial and intermittent streams and all stream restorations. The design certification must certify that the design meets the design requirements of this section and any design criteria set by the regulatory authority. The construction certification must certify that the stream-channel diversion or stream restoration meets all construction requirements of this section and is in accordance with the approved design.

- (c) Diversion of miscellaneous flows. (1) Miscellaneous flows, which consist of all flows except for perennial and intermittent streams, may be diverted away from disturbed areas if required or approved by the regulatory authority. Miscellaneous flows shall include ground-water discharges and ephemeral streams.
- (2) The design, location, construction, maintenance, and removal of diversions of miscellaneous flows shall meet all of the performance standards set forth in paragraph (a) of this section.
- (3) The requirements of paragraph (a)(2)(ii) of this section shall be met when the temporary and permanent diversions for miscellaneous flows are designed so that the combination of channel, bank and flood-plain configuration is adequate to pass safely the peak runoff of a 2-year, 6-hour precipitation event for a temporary diversion and a 10-year, 6-hour precipitation event for a permanent diversion.

[48 FR 43993, Sept. 26, 1983, as amended at 73 FR 75884, Dec. 12, 2008]

§817.45 Hydrologic balance: Sediment control measures.

- (a) Appropriate sediment control measures shall be designed, constructed, and maintained using the best technology currently available to:
- (1) Prevent, to the extent possible, additional contributions of sediment to stream flow or to runoff outside the permit area,
- (2) Meet the more stringent of applicable State or Federal effluent limitations
- (3) Minimize erosion to the extent possible.
- (b) Sediment control measures include practices carried out within and

adjacent to the disturbed area. The sedimentation storage capacity of practices in and downstream from the disturbed areas shall reflect the degree to which successful mining and reclamation techniques are applied to reduce erosion and control sediment. Sediment control measures consist of the utilization of proper mining and reclamation methods and sediment control practices, singly or in combination. Sediment control methods include but are not limited to—

- (1) Disturbing the smallest practicable area at any one time during the mining operation through progressive backfilling, grading, and prompt revegetation as required in §817.111(b);
- (2) Stabilizing the backfilled material to promote a reduction of the rate and volume of runoff in accordance with the requirements of §817.102;
- (3) Retaining sediment within disturbed areas:
- (4) Diverting runoff away from disturbed areas:
- (5) Diverting runoff using protected channels or pipes through disturbed areas so as not to cause additional erosion:
- (6) Using straw dikes, riprap, check dams, mulches, vegetative sediment filters, dugout ponds, and other measures that reduce overland flow velocity, reduce runoff volume, or trap sediment:
 - (7) Treating with chemicals; and
- (8) Treating mine drainage in underground sumps.

[44 FR 15422, Mar. 13, 1979, as amended at 48 FR 44781, Sept. 30, 1983]

§ 817.46 Hydrologic balance: Siltation structures.

- (a) For the purposes of this section only, disturbed areas shall not include those areas—
- (1) In which the only surface mining activities include diversion ditches, siltation structures, or roads that are designed, constructed and maintained in accordance with this part; and
- (2) For which the upstream area is not otherwise distributed by the operator.