

## Environmental Protection Agency

## § 63.7823

Q = Volumetric flow rate of stack gas, dry standard cubic foot per hour (dscf/hr);

P = Production rate of sinter during the test run, tons/hr; and

K = Conversion factor, 7,000 grains per pound (gr/lb).

(d) If you apply two or more control devices in parallel to emissions from a sinter plant discharge end or a BOPF, compute the average flow-weighted concentration for each test run using Equation 2 of this section as follows:

$$C_w = \frac{\sum_{i=1}^n C_i Q_i}{\sum_{i=1}^n Q_i} \quad (\text{Eq. 2})$$

Where:

$C_w$  = Flow-weighted concentration, gr/dscf;

$C_i$  = Concentration of particulate matter from exhaust stream "i", gr/dscf; and

$Q_i$  = Volumetric flow rate of effluent gas from exhaust stream "i", dry standard cubic foot per minute (dscfm).

(e) For a control device applied to emissions from a blast furnace casthouse, sample for an integral number of furnace tapping operations sufficient to obtain at least 1 hour of sampling for each test run.

(f) For a primary emission control device applied to emissions from a BOPF with a closed hood system, sample only during the primary oxygen blow and do not sample during any subsequent reblows. Continue sampling for each run for an integral number of primary oxygen blows.

(g) For a primary emission control system applied to emissions from a BOPF with an open hood system and for a control device applied solely to secondary emissions from a BOPF, you must complete the requirements of paragraphs (g)(1) and (2) of this section:

(1) Sample only during the steel production cycle. Conduct sampling under conditions that are representative of normal operation. Record the start and end time of each steel production cycle and each period of abnormal operation; and

(2) Sample for an integral number of steel production cycles. The steel production cycle begins when the scrap is charged to the furnace and ends 3 min-

utes after the slag is emptied from the vessel into the slag pot.

(h) For a control device applied to emissions from BOPF shop ancillary operations (hot metal transfer, skimming, desulfurization, or ladle metallurgy), sample only when the operation(s) is being conducted.

(i) Subject to approval by the permitting authority, you may conduct representative sampling of stacks when there are more than three stacks associated with a process.

### § 63.7823 What test methods and other procedures must I use to demonstrate initial compliance with the opacity limits?

(a) You must conduct each performance test that applies to your affected source according to the requirements in § 63.7(h)(5) and the conditions detailed in paragraphs (b) through (d) of this section.

(b) You must conduct each visible emissions performance test such that the opacity observations overlap with the performance test for particulate matter.

(c) To determine compliance with the applicable opacity limit in Table 1 to this subpart for a sinter plant discharge end or a blast furnace casthouse:

(1) Using a certified observer, determine the opacity of emissions according to Method 9 in appendix A to part 60 of this chapter.

(2) Obtain a minimum of 30 6-minute block averages. For a blast furnace casthouse, make observations during tapping of the furnace. Tapping begins when the furnace is opened, usually by creating a hole near the bottom of the furnace, and ends when the hole is plugged.

(d) To determine compliance with the applicable opacity limit in Table 1 to this subpart for BOPF shops:

(1) For an existing BOPF shop:

(i) Using a certified observer, determine the opacity of emissions according to Method 9 in appendix A to part 60 of this chapter except as specified in paragraphs (d)(1)(ii) and (iii) of this section.

(ii) Instead of procedures in section 2.4 of Method 9 in appendix A to part 60 of this chapter, record observations to

**§ 63.7824**

**40 CFR Ch. I (7-1-13 Edition)**

the nearest 5 percent at 15-second intervals for at least three steel production cycles.

(iii) Instead of procedures in section 2.5 of Method 9 in appendix A to part 60 of this chapter, determine the 3-minute block average opacity from the average of 12 consecutive observations recorded at 15-second intervals.

(2) For a new BOPF shop housing a bottom-blown BOPF:

(i) Using a certified observer, determine the opacity of emissions according to Method 9 in appendix A to part 60 of this chapter.

(ii) Determine the highest and second highest sets of 6-minute block average opacities for each steel production cycle.

(3) For a new BOPF shop housing a top-blown BOPF:

(i) Determine the opacity of emissions according to the requirements for an existing BOPF shop in paragraphs (d)(1)(i) through (iii) of this section.

(ii) Determine the highest and second highest sets of 3-minute block average opacities for each steel production cycle.

(4) Opacity observations must cover the entire steel production cycle and must be made for at least three cycles. The steel production cycle begins when the scrap is charged to the furnace and ends 3 minutes after the slag is emptied from the vessel into the slag pot.

(5) Determine and record the starting and stopping times of the steel production cycle.

(e) To determine compliance with the applicable opacity limit in Table 1 to this subpart for a sinter cooler at an existing sinter plant:

(1) Using a certified observer, determine the opacity of emissions according to Method 9 in appendix A to part 60 of this chapter.

(2) Obtain a minimum of 30 6-minute block averages.

(3) Make visible emission observations of uncovered portions of sinter plant coolers with the observer's line of sight generally in the direction of the center of the cooler.

[68 FR 27663, May 20, 2003, as amended at 71 FR 39586, July 13, 2006]

**§ 63.7824 What test methods and other procedures must I use to establish and demonstrate initial compliance with operating limits?**

(a) For each capture system subject to an operating limit in § 63.7790(b)(1), you must certify that the system operated during the performance test at the site-specific operating limits established in your operation and maintenance plan using the procedures in paragraphs (a)(1) through (4) of this section.

(1) Concurrent with all opacity observations, measure and record values for each of the operating limit parameters in your capture system operation and maintenance plan according to the monitoring requirements specified in § 63.7830(a).

(2) For any dampers that are manually set and remain at the same position at all times the capture system is operating, the damper position must be visually checked and recorded at the beginning and end of each opacity observation period segment.

(3) Review and record the monitoring data. Identify and explain any times the capture system operated outside the applicable operating limits.

(4) Certify in your performance test report that during all observation period segments, the capture system was operating at the values or settings established in your capture system operation and maintenance plan.

(b) For a venturi scrubber subject to operating limits for pressure drop and scrubber water flow rate in § 63.7790(b)(2), you must establish site-specific operating limits according to the procedures in paragraphs (b)(1) and (2) of this section. You may establish the parametric monitoring limit during the initial performance test or during any other performance test run that meets the emission limit.

(1) Using the CPMS required in § 63.7830(c), measure and record the pressure drop and scrubber water flow rate during each run of the particulate matter performance test.

(2) Compute and record the hourly average pressure drop and scrubber water flow rate for each individual test run. Your operating limits are the lowest average pressure drop and scrubber water flow rate value in any of the