

Environmental Protection Agency

Pt. 62, Subpt. FFF, Table 5

| | | |
|---|--|-----------------------------------|
| Municipal waste combustor technology | Carbon monoxide emissions level (parts per million by volume) ^a | Averaging time (hrs) ^b |
| Spreader stoker coal/refuse-derived fuel mixed fuel-fired combustor | 200 | 24 |

^a Measured at the combustor outlet in conjunction with a measurement of oxygen concentration, corrected to 7 percent oxygen, dry basis. Calculated as an arithmetic average.

^b Averaging times are 4-hour or 24-hour block averages.

^c 24-hour block average, geometric mean.

[69 FR 42121, July 14, 2004]

TABLE 4 TO SUBPART FFF OF PART 62—GENERIC COMPLIANCE SCHEDULE AND INCREMENTS OF PROGRESS (PRE-1987 MWCS)^{A B}

| Affected facilities | Increment 1 Submit final control plan | Increment 2 Award contracts | Increment 3 Begin on-site construction | Increment 4 Complete on-site construction | Increment 5 Final compliance |
|---|--|--------------------------------|---|--|---------------------------------|
| Affected facilities that commenced construction, modification, or reconstruction on or before June 26, 1987 (All pollutants). | January 11, 1999 | 05/18/99 | 11/16/99 | 11/19/00 | 12/19/00 |

^a Table 4 or 5 of this subpart applies to MWC units subject to the Federal plan except those with site-specific compliance schedules shown in Table 6 of this subpart.

^b As an alternative to this schedule, the owner or operator may close the affected facility by December 19, 2000, complete the retrofit while the affected facility is closed, and achieve final compliance upon restarting. See §§ 62.14108(c), 62.14108(d), and 62.14109(i) of this subpart.

TABLE 5 TO SUBPART FFF OF PART 62—GENERIC COMPLIANCE SCHEDULES AND INCREMENTS OF PROGRESS [Post-1987 MWCS]^{a b}

| Affected facilities | Increment 1 Submit final control plan | Increment 2 Award contracts | Increment 3 Begin on-site construction | Increment 4 Complete on-site construction | Increment 5 Final compliance |
|--|--|--------------------------------|---|--|---|
| Affected facilities that commenced construction modification, or reconstruction after June 26, 1987: | | | | | |
| 1. Emission limits for Hg, dioxin/furan | NA ^c | NA ^c | NA ^c | NA ^c | 11/12/99 or 1 year after permit issuance ^{d,e} |
| 2. Emission limits for SO ₂ , HCl, PM, Pb, Cd, opacity CO, NO _x . | January 11, 1999. | 05/18/99 | 11/16/99 | 11/19/00 | 12/19/00. |

^a Table 4 or 5 of this subpart applies to MWC units subject to the Federal plan except those with site-specific compliance schedules shown in table 6 of this subpart.

^b As an alternative to this schedule, the unit may close by December 19, 2000, complete retrofit while closed, and achieve final compliance upon restarting. See §§ 62.14108(c), 62.14108(d), and 62.14109(i) of this subpart.

^c Because final compliance is achieved in 1 year, no increments of progress are required.

^d Permit issuance is issuance of a revised construction permit or revised operating permit, if a permit modification is required to retrofit controls.

^e Final compliance must be achieved no later than December 19, 2000, even if the date "1 year after permit issuance" exceeds December 19, 2000.

[63 FR 63202, Nov. 12, 1998, as amended at 65 FR 33468, May 24, 2000]