

not exceed 70 percent of the burst pressure of the conductor casing or 70 percent of the collapse pressure of the cap rock casing.

(b) *Drive or structural casing.* This casing shall be set by driving, jetting, or drilling to a minimum depth of 100 feet below the mud line or such other depth, as may be required or approved by the District Manager, in order to support unconsolidated deposits and to provide hole stability for initial drilling operations. If this portion of the hole is drilled, a quantity of cement sufficient to fill the annular space back to the mud line shall be used.

(c) *Conductor and cap rock casing setting and cementing requirements.* (1) Conductor and cap rock casing design and setting depths shall be based upon relevant engineering and geologic factors including the presence or absence of hydrocarbons, potential hazards, and water depths. The proposed casing setting depths may be varied, subject to District Manager approval, to permit the casing to be set in a competent formation or through formations determined desirable to be isolated from the wellbore by casing for safer drilling operations. However, the conductor casing shall be set immediately prior to drilling into formations known to contain oil or gas or, if unknown, upon encountering such formations. Cap rock casing shall be set and cemented through formations known to contain oil or gas or, if unknown, upon encountering such formations. Upon encountering unexpected formation pressures, the lessee shall submit a revised casing program to the District Manager for approval.

(2) Conductor casing shall be cemented with a quantity of cement that fills the calculated annular space back to the mud line. Cement fill shall be verified by the observation of cement returns. In the event that observation of cement returns is not feasible, additional quantities of cement shall be used to assure fill to the mud line.

(3) Cap rock casing shall be cemented with a quantity of cement that fills the calculated annular space to at least 200 feet inside the conductor casing. When geologic conditions such as near surface fractures and faulting exist, cap rock casing shall be cemented with a

quantity of cement that fills the calculated annular space to the mud line, unless otherwise approved by the District Manager. In brine wells, the second cap rock casing shall be cemented with a quantity of cement that fills the calculated annular space to at least 200 feet above the setting depth of the first cap rock casing.

(d) *Bobtail cap rock casing setting and cementing requirements.* (1) Bobtail cap rock casing shall be set on or just in cap rock and lapped a minimum of 100 feet into the previous casing string.

(2) Sufficient cement shall be used to fill the annular space to the top of the bobtail cap rock casing.

(e) *Production liner setting and cementing requirements.* (1) Production liners for sulphur wells and bleedwells shall be set in cap rock at or above the bottom of the open hole (hole that is open in cap rock, below the bottom of the cap rock casing) and lapped into the previous casing string or to the surface. For brine wells, the liner shall be set in salt and lapped into the previous casing string or to the surface.

(2) The production liner is not required to be cemented unless the cap rock contains oil or gas. If the cap rock contains oil or gas, sufficient cement shall be used to fill the annular space to the top of the production liner.

#### § 250.1609 Pressure testing of casing.

(a) Prior to drilling the plug after cementing, all casing strings, except the drive or structural casing, shall be pressure tested. The conductor casing shall be tested to at least 200 psi. All casing strings below the conductor casing shall be tested to 500 psi or 0.22 psi/ft, whichever is greater. (When oil or gas is not present in the cap rock, the production liner need not be cemented in place; thus, it would not be subject to pressure testing.) If the pressure declines more than 10 percent in 30 minutes or if there is another indication of a leak, the casing shall be recemented, repaired, or an additional casing string run and the casing tested again. The above procedures shall be repeated until a satisfactory test is obtained. The time, conditions of testing, and results of all casing pressure tests shall be recorded in the driller's report.

(b) After cementing any string of casing other than structural, drilling shall not be resumed until there has been a timelapse of at least 8 hours under pressure for the conductor casing string or 12 hours under pressure for all other casing strings. Cement is considered under pressure if one or more float valves are shown to be holding the cement in place or when other means of holding pressure are used.

**§250.1610 Blowout preventer systems and system components.**

(a) *General.* The blowout preventer (BOP) systems and system components shall be designed, installed, used, maintained, and tested to assure well control.

(b) *BOP stacks.* The BOP stacks shall consist of an annular preventer and the number of ram-type preventers as specified under paragraphs (e) and (f) of this section. The pipe rams shall be of proper size to fit the drill pipe in use.

(c) *Working pressure.* The working-pressure rating of any BOP shall exceed the surface pressure to which it may be anticipated to be subjected.

(d) *BOP equipment.* All BOP systems shall be equipped and provided with the following:

(1) An accumulator system that provides sufficient capacity to supply 1.5 times the volume necessary to close and hold closed all BOP equipment units with a minimum pressure of 200 psi above the precharge pressure, without assistance from a charging system. Accumulator regulators supplied by rig air that do not have a secondary source of pneumatic supply must be equipped with manual overrides or other devices alternately provided to ensure capability of hydraulic operations if rig air is lost.

(2) An automatic backup to the accumulator system. The backup system shall be supplied by a power source independent from the power source to the primary accumulator system. The automatic backup system shall possess sufficient capability to close the BOP and hold it closed.

(3) At least one operable remote BOP control station in addition to the one on the drilling floor. This control station shall be in a readily accessible location away from the drilling floor.

(4) A drilling spool with side outlets, if side outlets are not provided in the body of the BOP stack, to provide for separate kill and choke lines.

(5) A choke line and a kill line each equipped with two full-opening valves. At least one of the valves on the choke line and one valve on the kill line shall be remotely controlled, except that a check valve may be installed on the kill line in lieu of the remotely controlled valve, provided that two readily accessible manual valves are in place and the check valve is placed between the manual valve and the pump.

(6) A fill-up line above the uppermost preventer.

(7) A choke manifold designed with consideration of anticipated pressures to which it may be subjected, method of well control to be employed, surrounding environment, and corrosiveness, volume, and abrasiveness of fluids. The choke manifold shall also meet the following requirements:

(i) Manifold and choke equipment subject to well and/or pump pressure shall have a rated working pressure at least as great as the rated working pressure of the ram-type BOP's or as otherwise approved by the District Manager;

(ii) All components of the choke manifold system shall be protected from freezing by heating, draining, or filling with proper fluids; and

(iii) When buffer tanks are installed downstream of the choke assemblies for the purpose of manifolding the bleed lines together, isolation valves shall be installed on each line.

(8) Valves, pipes, flexible steel hoses, and other fittings upstream of, and including, the choke manifold with a pressure rating at least as great as the rated working pressure of the ram-type BOP's unless otherwise approved by the District Manager.

(9) A wellhead assembly with a rated working pressure that exceeds the pressure to which it might be subjected.

(10) The following system components:

(i) A kelly cock (an essentially full-opening valve) installed below the swivel and a similar valve of such design that it can be run through the BOP stack installed at the bottom of the kelly. A wrench to fit each valve