

acceptable as guidelines in complying with this requirement.

(f) The lessee shall record pressure conditions during BOP tests on pressure charts, unless otherwise approved by the District Manager. The test duration for each BOP component tested shall be sufficient to demonstrate that the component is effectively holding pressure. The charts shall be certified as correct by the operator's representative at the facility.

(g) The time, date, and results of all pressure tests, actuations, inspections, and crew drills of the BOP system and system components shall be recorded in the driller's report. The BOP tests shall be documented in accordance with the following:

(1) The documentation shall indicate the sequential order of BOP and auxiliary equipment testing and the pressure and duration of each test. As an alternate, the documentation in the driller's report may reference a BOP test plan that contains the required information and is retained on file at the facility.

(2) The control station used during the test shall be identified in the driller's report.

(3) Any problems or irregularities observed during BOP and auxiliary equipment testing and any actions taken to remedy such problems or irregularities shall be noted in the driller's report.

(4) Documentation required to be entered in the driller's report may instead be referenced in the driller's report. All records, including pressure charts, driller's report, and referenced documents, pertaining to BOP tests, actuations, and inspections, shall be available for BSEE review at the facility for the duration of the drilling activity. Following completion of the drilling activity, all drilling records shall be retained for a period of 2 years at the facility, at the lessee's field office nearest the OCS facility, or at another location conveniently available to the District Manager.

#### §250.1612 Well-control drills.

Well-control drills shall be conducted for each drilling crew in accordance with the requirements set forth in §250.462 of this part or as approved by the District Manager.

#### §250.1613 Diverter systems.

(a) When drilling a conductor or cap rock hole, all drilling units shall be equipped with a diverter system consisting of a diverter sealing element, diverter lines, and control systems. The diverter system shall be designed, installed, and maintained so as to divert gases, water, mud, and other materials away from the facilities and personnel.

(b) The diverter system shall be equipped with remote-control valves in the flow lines that can be operated from at least one remote-control station in addition to the one on the drilling floor. Any valve used in a diverter system shall be full opening. No manual or butterfly valves shall be installed in any part of a diverter system. There shall be a minimum number of turns in the vent line(s) downstream of the spool outlet flange, and the radius of curvature of turns shall be as large as practicable. Flexible hose may be used for diversion lines instead of rigid pipe if the flexible hose has integral end couplings. The entire diverter system shall be firmly anchored and supported to prevent whipping and vibrations. All diverter control equipment and lines shall be protected from physical damage from thrown and falling objects.

(c) For drilling operations conducted with a surface wellhead configuration, the following shall apply:

(1) If the diverter system utilizes only one spool outlet, branch lines shall be installed to provide downwind diversion capability, and

(2) No spool outlet or diverter line internal diameter shall be less than 10 inches, except that dual spool outlets are acceptable if each outlet has a minimum internal diameter of 8 inches, and both outlets are piped to overboard lines and that each line downstream of the changeover nipple at the spool has a minimum internal diameter of 10 inches.

(d) The diverter sealing element and diverter valves shall be pressure tested to a minimum of 200 psi when nipped upon conductor casing. No more than 7 days shall elapse between subsequent pressure tests. The diverter sealing element, diverter valves, and diverter control systems (including the remote)

#### § 250.1614

shall be actuation tested, and the diverter lines shall be tested for flow prior to spudding and thereafter at least once each 24-hour period alternating between control stations. All test times and results shall be recorded in the driller's report.

#### § 250.1614 Mud program.

(a) The quantities, characteristics, use, and testing of drilling mud and the related drilling procedures shall be designed and implemented to prevent the loss of well control.

(b) The lessee shall comply with requirements concerning mud control, mud test and monitoring equipment, mud quantities, and safety precautions in enclosed mud handling areas as prescribed in §§ 250.455 through 250.459 of this part, except that the installation of an operable degasser in the mud system as required in § 250.456(g) is not required for sulphur operations.

#### § 250.1615 Securing of wells.

A downhole-safety device such as a cement plug, bridge plug, or packer shall be timely installed when drilling operations are interrupted by events such as those that force evacuation of the drilling crew, prevent station keeping, or require repairs to major drilling units or well-control equipment. The use of blind-shear rams or pipe rams and an inside BOP may be approved by the District Manager in lieu of the above requirements if cap rock casing has been set.

#### § 250.1616 Supervision, surveillance, and training.

(a) The lessee shall provide onsite supervision of drilling operations at all times.

(b) From the time drilling operations are initiated and until the well is completed or abandoned, a member of the drilling crew or the toolpusher shall maintain rig-floor surveillance continuously, unless the well is secured with BOP's, bridge plugs, packers, or cement plugs.

(c) Lessee and drilling contractor personnel shall be trained and qualified in accordance with the provisions of subpart O of this part. Records of specific training that lessee and drilling contractor personnel have successfully

#### 30 CFR Ch. II (7-1-14 Edition)

completed, the dates of completion, and the names and dates of the courses shall be maintained at the drill site.

#### § 250.1617 Application for permit to drill.

(a) Before drilling a well under a BOEM-approved Exploration Plan, Development and Production Plan, or Development Operations Coordination Document, you must file Form BSEE-0123, APD, with the District Manager for approval. The submission of your APD must be accompanied by payment of the service fee listed in § 250.125. Before starting operations, you must receive written approval from the District Manager unless you received oral approval under § 250.140.

(b) An APD shall include rated capacities of the proposed drilling unit and of major drilling equipment. After a drilling unit has been approved for use in a BSEE district, the information need not be resubmitted unless required by the District Manager or there are changes in the equipment that affect the rated capacity of the unit.

(c) An APD shall include a fully completed Form BSEE-0123 and the following:

(1) A plat, drawn to a scale of 2,000 feet to the inch, showing the surface and subsurface location of the well to be drilled and of all the wells previously drilled in the vicinity from which information is available. For development wells on a lease, the wells previously drilled in the vicinity need not be shown on the plat. Locations shall be indicated in feet from the nearest block line;

(2) The design criteria considered for the well and for well control, including the following:

- (i) Pore pressure;
- (ii) Formation fracture gradients;
- (iii) Potential lost circulation zones;
- (iv) Mud weights;
- (v) Casing setting depths;
- (vi) Anticipated surface pressures (which for purposes of this section are defined as the pressure that can reasonably be expected to be exerted upon a casing string and its related wellhead equipment). In the calculation of anticipated surface pressure, the lessee shall take into account the drilling,