

## § 250.501

leased and not leased), the National security or defense, or the marine, coastal, or human environment.

### § 250.501 Definition.

When used in this subpart, the following term shall have the meaning given below:

*Well-completion operations* means the work conducted to establish the production of a well after the production-casing string has been set, cemented, and pressure-tested.

### § 250.502 Equipment movement.

The movement of well-completion rigs and related equipment on and off a platform or from well to well on the same platform, including rigging up and rigging down, shall be conducted in a safe manner. All wells in the same well-bay which are capable of producing hydrocarbons shall be shut in below the surface with a pump-through-type tubing plug and at the surface with a closed master valve prior to moving well-completion rigs and related equipment, unless otherwise approved by the District Manager. A closed surface-controlled subsurface safety valve of the pump-through type may be used in lieu of the pump-through-type tubing plug, provided that the surface control has been locked out of operation. The well from which the rig or related equipment is to be moved shall also be equipped with a back-pressure valve prior to removing the blowout preventer (BOP) system and installing the tree.

### § 250.503 Emergency shutdown system.

When well-completion operations are conducted on a platform where there are other hydrocarbon-producing wells or other hydrocarbon flow, an emergency shutdown system (ESD) manually controlled station shall be installed near the driller's console or well-servicing unit operator's work station.

### § 250.504 Hydrogen sulfide.

When a well-completion operation is conducted in zones known to contain hydrogen sulfide (H<sub>2</sub>S) or in zones where the presence of H<sub>2</sub>S is unknown (as defined in §250.490 of this part), the lessee shall take appropriate pre-

## 30 CFR Ch. II (7-1-14 Edition)

cautions to protect life and property on the platform or completion unit, including, but not limited to operations such as blowing the well down, dismantling wellhead equipment and flow lines, circulating the well, swabbing, and pulling tubing, pumps, and packers. The lessee shall comply with the requirements in §250.490 of this part as well as the appropriate requirements of this subpart.

### § 250.505 Subsea completions.

No subsea well completion shall be commenced until the lessee obtains written approval from the District Manager in accordance with §250.513 of this part. That approval shall be based upon a case-by-case determination that the proposed equipment and procedures will adequately control the well and permit safe production operations.

### § 250.506 Crew instructions.

Prior to engaging in well-completion operations, crew members shall be instructed in the safety requirements of the operations to be performed, possible hazards to be encountered, and general safety considerations to protect personnel, equipment, and the environment. Date and time of safety meetings shall be recorded and available at the facility for review by BSEE representatives.

### §§ 250.507-250.508 [Reserved]

### § 250.509 Well-completion structures on fixed platforms.

Derricks, masts, substructures, and related equipment shall be selected, designed, installed, used, and maintained so as to be adequate for the potential loads and conditions of loading that may be encountered during the proposed operations. Prior to moving a well-completion rig or equipment onto a platform, the lessee shall determine the structural capability of the platform to safely support the equipment and proposed operations, taking into consideration the corrosion protection, age of platform, and previous stresses to the platform.

### § 250.510 Diesel engine air intakes.

Diesel engine air intakes must be equipped with a device to shut down

## Safety & Environmental Enforcement, Interior

## § 250.514

the diesel engine in the event of runaway. Diesel engines that are continuously attended must be equipped with either remote operated manual or automatic-shutdown devices. Diesel engines that are not continuously attended must be equipped with automatic-shutdown devices.

### § 250.511 Traveling-block safety device.

All units being used for well-completion operations that have both a traveling block and a crown block must be equipped with a safety device that is designed to prevent the traveling block from striking the crown block. The device must be checked for proper operation weekly and after each drill-line slipping operation. The results of the operational check must be entered in the operations log.

### § 250.512 Field well-completion rules.

When geological and engineering information available in a field enables the District Manager to determine specific operating requirements, field well-completion rules may be established on the District Manager's initiative or in response to a request from a lessee. Such rules may modify the specific requirements of this subpart. After field well-completion rules have been established, well-completion operations in the field shall be conducted in accordance with such rules and other requirements of this subpart. Field well-completion rules may be amended or canceled for cause at any time upon the initiative of the District Manager or upon the request of a lessee.

### § 250.513 Approval and reporting of well-completion operations.

(a) No well-completion operation may begin until the lessee receives written approval from the District Manager. If completion is planned and the data are available at the time you submit the Application for Permit to Drill and Supplemental APD Information Sheet (Forms BSEE-0123 and BSEE-0123S), you may request approval for a well-completion on those forms (see §§ 250.410 through 250.418 of this part). If the District Manager has not approved the completion or if the completion objective or plans have sig-

nificantly changed, you must submit an Application for Permit to Modify (Form BSEE-0124) for approval of such operations.

(b) You must submit the following with Form BSEE-0124 (or with Form BSEE-0123; Form BSEE-0123S):

(1) A brief description of the well-completion procedures to be followed, a statement of the expected surface pressure, and type and weight of completion fluids;

(2) A schematic drawing of the well showing the proposed producing zone(s) and the subsurface well-completion equipment to be used;

(3) For multiple completions, a partial electric log showing the zones proposed for completion, if logs have not been previously submitted;

(4) All applicable information required in § 250.515.

(5) When the well-completion is in a zone known to contain H<sub>2</sub>S or a zone where the presence of H<sub>2</sub>S is unknown, information pursuant to § 250.490 of this part; and

(6) Payment of the service fee listed in § 250.125.

(c) Within 30 days after completion, you must submit to the District Manager an End of Operations Report (Form BSEE-0125), including a schematic of the tubing and subsurface equipment.

(d) You must submit public information copies of Form BSEE-0125 according to § 250.186.

[76 FR 64462, Oct. 18, 2011, as amended at 77 FR 50894, Aug. 22, 2012]

### § 250.514 Well-control fluids, equipment, and operations.

(a) Well-control fluids, equipment, and operations shall be designed, utilized, maintained, and/or tested as necessary to control the well in foreseeable conditions and circumstances, including subfreezing conditions. The well shall be continuously monitored during well-completion operations and shall not be left unattended at any time unless the well is shut in and secured.

(b) The following well-control-fluid equipment shall be installed, maintained, and utilized:

(1) A fill-up line above the uppermost BOP;