

(5) Procedures for monitoring process and control device parameters.

(6) Corrective actions to be taken when process or operating parameters or add-on control device parameters deviate from the operating limits specified in Table 2 to this subpart, including:

(i) Procedures to determine and record the cause of a deviation or excursion, and the time the deviation or excursion began and ended; and

(ii) Procedures for recording the corrective action taken, the time corrective action was initiated, and the time and date the corrective action was completed.

(7) A maintenance schedule for each emission unit and control device that is consistent with the manufacturer's instructions and recommendations for routine and long-term maintenance.

(e) You must develop a written start-up, shutdown, and malfunction plan (SSMP) according to the provisions in § 63.6(e)(3).

[69 FR 416, Jan. 5, 2004, as amended at 71 FR 20467, Apr. 20, 2006]

TESTING AND INITIAL COMPLIANCE REQUIREMENTS

§ 63.7110 By what date must I conduct performance tests and other initial compliance demonstrations?

(a) If you have an existing affected source, you must complete all applicable performance tests within January 5, 2007, according to the provisions in §§ 63.7(a)(2) and 63.7114.

(b) If you have a new affected source, and commenced construction or reconstruction between December 20, 2002, and January 5, 2004, you must demonstrate initial compliance with either the proposed emission limitation or the promulgated emission limitation no later than 180 calendar days after January 5, 2004 or within 180 calendar days after startup of the source, whichever is later, according to §§ 63.7(a)(2)(ix) and 63.7114.

(c) If you commenced construction or reconstruction between December 20, 2002, and January 5, 2004, and you chose to comply with the proposed emission limitation when demonstrating initial compliance, you must conduct a demonstration of compliance with the pro-

mulgated emission limitation within January 5, 2007 or after startup of the source, whichever is later, according to §§ 63.7(a)(2)(ix) and 63.7114.

(d) For each initial compliance requirement in Table 3 to this subpart that applies to you where the monitoring averaging period is 3 hours, the 3-hour period for demonstrating continuous compliance for emission units within existing affected sources at LMP begins at 12:01 a.m. on the compliance date for existing affected sources, that is, the day following completion of the initial compliance demonstration, and ends at 3:01 a.m. on the same day.

(e) For each initial compliance requirement in Table 3 to this subpart that applies to you where the monitoring averaging period is 3 hours, the 3-hour period for demonstrating continuous compliance for emission units within new or reconstructed affected sources at LMP begins at 12:01 a.m. on the day following completion of the initial compliance demonstration, as required in paragraphs (b) and (c) of this section, and ends at 3:01 a.m. on the same day.

§ 63.7111 When must I conduct subsequent performance tests?

You must conduct a performance test within 5 years following the initial performance test and within 5 years following each subsequent performance test thereafter.

§ 63.7112 What performance tests, design evaluations, and other procedures must I use?

(a) You must conduct each performance test in Table 4 to this subpart that applies to you.

(b) Each performance test must be conducted according to the requirements in § 63.7(e)(1) and under the specific conditions specified in Table 4 to this subpart.

(c) You may not conduct performance tests during periods of startup, shutdown, or malfunction, as specified in § 63.7(e)(1).

(d) Except for opacity and VE observations, you must conduct three separate test runs for each performance test required in this section, as specified in § 63.7(e)(3). Each test run must last at least 1 hour.