

## § 63.7826

initial compliance if the 30-day rolling average of the oil content of the feedstock, measured during the initial performance test in accordance with § 63.7824(d) is no more than 0.02 percent. For each existing or new sinter plant subject to the alternative operating limit in § 63.7790(d)(2), you have demonstrated initial compliance if the 30-day rolling average of the volatile organic compound emissions from the sinter plant windbox exhaust stream, measured during the initial performance test in accordance with § 63.7824(e) is no more than 0.2 lb/ton of sinter produced.

(c) For each emission limitation that applies to you, you must submit a notification of compliance status according to § 63.7840(e).

[68 FR 27663, May 20, 2003, as amended at 71 FR 39586, July 13, 2006]

### **§ 63.7826 How do I demonstrate initial compliance with the operation and maintenance requirements that apply to me?**

(a) For a capture system applied to emissions from a sinter plant discharge end or blast furnace casthouse or to secondary emissions from a BOPF, you have demonstrated initial compliance if you meet all of the conditions in paragraphs (a)(1) through (4) of this section.

(1) Prepared the capture system operation and maintenance plan according to the requirements of § 63.7800(b), including monthly inspection procedures and detailed descriptions of the operating parameter(s) selected to monitor the capture system;

(2) Certified in your performance test report that the system operated during the test at the operating limits established in your operation and maintenance plan;

(3) Submitted a notification of compliance status according to the requirements in § 63.7840(e), including a copy of the capture system operation and maintenance plan and your certification that you will operate the capture system at the values or settings established for the operating limits in that plan; and

(4) Prepared a site-specific monitoring plan according to the requirements in § 63.7831(a).

## 40 CFR Ch. I (7–1–14 Edition)

(b) For each control device subject to operating limits in § 63.7790(b)(2) or (3), you have demonstrated initial compliance if you meet all the conditions in paragraphs (b)(1) through (3) of this section.

(1) Prepared the control device operation and maintenance plan according to the requirements of § 63.7800(b), including a preventative maintenance schedule and, as applicable, detailed descriptions of the corrective action procedures for baghouses and other control devices;

(2) Submitted a notification of compliance status according to the requirements in § 63.7840(e), including a copy of the operation and maintenance plan; and

(3) Prepared a site-specific monitoring plan according to the requirements in § 63.7831(a).

[68 FR 27663, May 20, 2003, as amended at 71 FR 39586, July 13, 2006]

## CONTINUOUS COMPLIANCE REQUIREMENTS

### **§ 63.7830 What are my monitoring requirements?**

(a) For each capture system subject to an operating limit in § 63.7790(b)(1) established in your capture system operation and maintenance plan, you must install, operate, and maintain a CPMS according to the requirements in § 63.7831(e) and the requirements in paragraphs (a)(1) through (3) of this section.

(1) Dampers that are manually set and remain in the same position are exempt from the requirement to install and operate a CPMS. If dampers are not manually set and remain in the same position, you must make a visual check at least once every 24 hours to verify that each damper for the capture system is in the same position as during the initial performance test.

(2) If you use a flow measurement device to monitor the operating limit parameter for a sinter plant discharge end or blast furnace casthouse, you must monitor the hourly average rate (*e.g.*, the hourly average actual volumetric flow rate through each separately ducted hood, the average hourly total volumetric flow rate at the inlet to the control device) according to the requirements in § 63.7832.

(3) If you use a flow measurement device to monitor the operating limit parameter for a capture system applied to secondary emissions from a BOPF, you must monitor the average rate for each steel production cycle (*e.g.*, the average actual volumetric flow rate through each separately ducted hood for each steel production cycle, the average total volumetric flow rate at the inlet to the control device for each steel production cycle) according to the requirements in § 63.7832.

(b) Except as provided in paragraph (b)(3) of this section, you must meet the requirements in paragraph (b)(1) or (2) of this section for each baghouse applied to meet any particulate emission limit in Table 1 to this subpart. You must conduct inspections of each baghouse according to the requirements in paragraph (b)(4) of this section.

(1) Install, operate, and maintain a bag leak detection system according to § 63.7831(f) and monitor the relative change in particulate matter loadings according to the requirements in § 63.7832; or

(2) If you do not install and operate a bag leak detection system, you must install, operate, and maintain a COMS according to the requirements in § 63.7831(h) and monitor the hourly average opacity of emissions exiting each control device stack according to the requirements in § 63.7832.

(3) A bag leak detection system and COMS are not required for a baghouse that meets the requirements in paragraphs (b)(3)(i) and (ii) of this section.

(i) The baghouse is a positive pressure baghouse and is not equipped with exhaust gas stacks; and

(ii) The baghouse was installed before August 30, 2005.

(4) You must conduct inspections of each baghouse at the specified frequencies according to the requirements in paragraphs (b)(4)(i) through (viii) of this section.

(i) Monitor the pressure drop across each baghouse cell each day to ensure pressure drop is within the normal operating range identified in the manual.

(ii) Confirm that dust is being removed from hoppers through weekly visual inspections or other means of

ensuring the proper functioning of removal mechanisms.

(iii) Check the compressed air supply for pulse-jet baghouses each day.

(iv) Monitor cleaning cycles to ensure proper operation using an appropriate methodology.

(v) Check bag cleaning mechanisms for proper functioning through monthly visual inspection or equivalent means.

(vi) Make monthly visual checks of bag tension on reverse air and shaker-type baghouses to ensure that bags are not kinked (kneaded or bent) or laying on their sides. You do not have to make this check for shaker-type baghouses using self-tensioning (spring-loaded) devices.

(vii) Confirm the physical integrity of the baghouse through quarterly visual inspections of the baghouse interior for air leaks.

(viii) Inspect fans for wear, material buildup, and corrosion through quarterly visual inspections, vibration detectors, or equivalent means.

(c) For each venturi scrubber subject to the operating limits for pressure drop and scrubber water flow rate in § 63.7790(b)(2), you must install, operate, and maintain CPMS according to the requirements in § 63.7831(g) and monitor the hourly average pressure drop and water flow rate according to the requirements in § 63.7832.

(d) For each electrostatic precipitator subject to the opacity operating limit in § 63.7790(b)(3), you must install, operate, and maintain a COMS according to the requirements in § 63.7831(h) and monitor the hourly average opacity of emissions exiting each control device stack according to the requirements in § 63.7832.

(e) For each sinter plant subject to the operating limit in § 63.7790(d), you must either:

(1) Compute and record the 30-day rolling average of the oil content of the feedstock for each operating day using the procedures in § 63.7824(d); or

(2) Compute and record the 30-day rolling average of the volatile organic compound emissions (lbs/ton of sinter) for each operating day using the procedures in § 63.7824(e).

[68 FR 27663, May 20, 2003, as amended at 71 FR 39586, July 13, 2006]